

<u>Project measures</u>		<u>Municipality/Consult.</u>	
<p>a) Construction of a central wastewater treatment plant (for approx. 50,000 inh, capacity 7,500 m³/d); according to the present conception two-stage biological plant with sludge digesting, sludge dehydration and biogas utilization;</p> <p>b) Construction of a system for the conveyance of treated wastewater to the neighbouring Wadi Abu el Feed (pumping station, Q = 100 l/s; pressure pipe DN 250, length 4.5 km; seasonal reservoir with a volume of approx. 100 000 m³);</p>	<p>a) - b):</p> <p>Compliance with the project concept and with the planned schedule of time, cost and financing</p>	<p>a) - b):</p> <p>Reporting by the Municipality and the Consultant</p>	<p>a) - b):</p> <p>Quarterly progress reports of the Municipality and the Consultant</p>

05.1998
9:42
KEM HRI.LIH